



**NOTES:**

1. COOPERATIVE FURNISHED AND INSTALLED POLE.
2. COOPERATIVE METER PAN FURNISHED BY COOPERATIVE AND INSTALLED BY MEMBER.
3. WEATHERPROOF MAIN DISCONNECT, FURNISHED, INSTALLED, AND MAINTAINED BY MEMBER.
4. CONDUIT, FITTINGS, AND CONDUCTOR FURNISHED, INSTALLED AND MAINTAINED BY MEMBER AND SIZED AS FOLLOWS :

100 AMP INSTALLATION : 1 1/4" CONDUIT & NIPPLE, MINIMUM #2 AWG  
COPPER 600 VOLT DIRECT BURIAL CONDUCTOR.

200 AMP INSTALLATION : 2" CONDUIT & NIPPLE, MINIMUM # 3/0 AWG  
COPPER 600 VOLT DIRECT BURIAL CONDUCTOR .

5. TRENCH FOR UNDERGROUND SERVICE TO BE 36 INCHES BELOW GRADE .
6. CONDUIT SHALL EXTEND 24 INCHES BEYOND ANY SURFACE OBSTRUCTIONS (SIDEWALLS, DRIVEWAYS, ETC.)

## UNDERGROUND SERVICE FOR RESIDENCE

CONCORDIA ELECTRIC COOPERATIVE, INC.  
EXHIBIT "D" PROCEDURE NO. 701

REVISIONS		